

Summary Form for Electronic Document Submittal

Form F

Lead agencies may include 15 hardcopies of this document when submitting electronic copies of Environmental Impact Reports, Negative Declarations, Mitigated Negative Declarations, or Notices of Preparation to the State Clearinghouse (SCH). The SCH also accepts other summaries, such as EIR Executive Summaries prepared pursuant to CEQA Guidelines Section 15123. Please include one copy of the Notice of Completion Form (NOC) with your submission and attach the summary to each electronic copy of the document.

SCH #: 2026071144

Project Title: Heacock Street South Extension Project

Lead Agency: City of Moreno Valley

Contact Name: Quang Nguyen

Email: quangn@moval.org Phone Number: 951.413.3159

Project Location: Moreno Valley Riverside
City *County*

Project Description (Proposed actions, location, and/or consequences).

The proposed project would widen and realign Heacock Street in Moreno Valley between San Michele Road and the Perris Valley Storm Drainage Lateral "B" (channel) to a total width of 76 feet. The project proposes to extend Heacock Street's Arterial classification south from San Michele to the City limits. The project site is a total of 15 acres. Under the proposed project, 11.91 acres of the total 15-acre project site would be disturbed, this would include permanent new roadway and infrastructure improvements. The remaining 2.89 acres of the existing roadway would be temporarily disturbed. Heacock Street improvements would terminate in a cul-de-sac adjacent to and north of the channel. Storm drain improvements are also proposed in the project impact area and are included in the 11.91 acres of disturbance.

Identify the project's significant or potentially significant effects and briefly describe any proposed mitigation measures that would reduce or avoid that effect.

The proposed project would result in a less than significant impact with the incorporation of identified mitigation measures for biological resources, cultural resources, geology and soils, and tribal cultural resources. Summary of mitigation measures are provided below.

BIO-1 and BOI-2 (Wetland monitoring)

BIO-3 (Preconstruction Survey for Burrowing Owls)

CUL-1 and CUL-2 (Archaeological Monitoring and Archaeology Aeport)

CUL-3 and CUL-4 (Unanticipated discover of human remains and Non-Disclosure of Reburial Locations)

GEO-1 (Unanticipated discovery of Paleontological Resources)

TCR-1 (Native American monitor)

TCR-2 (Tribal Cultural Resource Monitoring Plan)

TCR-3 (Tribal Cultural Resource Disposition)

TCR-4 (Unanticipated discovery of archaeological or tribal cultural resources)

TCR-5 (Inadvertent Finds)

If applicable, describe any of the project's areas of controversy known to the Lead Agency, including issues raised by agencies and the public.

No areas of controversy concerning the proposed project have been identified.

Provide a list of the responsible or trustee agencies for the project.

Riverside County Flood Control and Water Conservation District (Encroachment permit for minor modifications to drainage improvements)